



बाणगङ्गा नगरपालिका
नगर कार्यपालिकाको कार्यालय
बाणगङ्गा, कपिलवस्तु
लुम्बिनी प्रदेश, नेपाल



पत्र संख्या: ०८२/०८३
चलानी नं.:

मिति: २०८३/०१/०४


विषय: प्लाष्टिक टनेल (न्याचुरल्ली भेन्टिलेटेड टप भेण्ट ग्रीनहाउस) निर्माणको दररेट (कोटेशन) उपलब्ध गराई दिने बारेको सूचना।

प्रस्तुत विषयमा बाणगंगा नगरपालिकाको चालु आ.व. २०८२/०८३ को वार्षिक स्वीकृत कार्यक्रम अनुसार प्लाष्टिक टनेल (न्याचुरल्ली भेन्टिलेटेड टप भेण्ट ग्रीनहाउस) निर्माण गर्नु पर्ने भएकोले नगरपालिकामा सूचिकृत रहेका फर्म/कम्पनी/सप्लायर्सहरूले सम्प्लगन स्पेसीफिकेशन तथा डिजाईन अनुसारको प्लाष्टिक टनेल (न्याचुरल्ली भेन्टिलेटेड टप भेण्ट ग्रीनहाउस) निर्माण गर्न सकिने दररेट (कोटेशन) १५ (पन्ध्र) दिन (मिति २०८३/०१/१८ गते) भित्र गोप्य सिलबन्दी गरी आवश्यक कागजात सहित उपलब्ध गराई दिनु हुन सम्बन्धित सरोकारवलाहरूमा यसै सूचनाद्वारा अनुरोध गरिन्छ।

सम्प्लगन गर्नुपर्ने आवश्यक कागजातहरू

१. फर्म/कम्पनी/सप्लायर्स दर्ता भएको दर्ता प्रमाण पत्रको प्रतिलिपी
२. आ.व. २०८१/०८२ को चुक्ता प्रमाण पत्रको प्रतिलिपी
३. स्थायी लेखा नम्बर (PAN/VAT) दर्ता प्रमाण पत्रको प्रतिलिपी
४. नागरिकताको प्रतिलिपी

नोट:- विस्तृत जानकारीका लागि बाणगंगा नगरपालिका, कृषि विकास शाखा कपिलवस्तुमा सम्पर्क राख्नुहोला।
सम्पर्क नम्बर-९८४१३५२७४७, ९८४७०५२९५४


भक्तिराम मरासिनी
प्रमुख प्रशासकीय अधिकृत

भक्तिराम मरासिनी
प्रमुख प्रशासकीय अधिकृत


Banganga Municipality
Office of Municipal Executive
Banganga, Kapilvastu
 सुनिवन्ती प्रदेश, नेपाल

Bill of Quantity

Project Name: न्याचुरल्ली भेन्टिलेटेड टप भेन्ट ग्रीनहाउस (कार्यालय परिषर भित्र)


Project site: बाणगङ्गा नगरपालिका, नगर कार्यपालिकाको कार्यालय

A. The rate quoted under here shall be inclusive of;

1. Supplying the materials along with accessories to the site
2. Fixing and erecting them in position as per standard practices, specification and instruction of site Engineer
3. Tests and maintenance up to the period, specified in the agreement.



B. The itemwise rate should be quoted without vat.

S.N.	Details of works	Unit	Quantity	Rate (Nrs.) Excluding VAT		Amount	Rmks
				In Figures	In words		
A)	CIVILS WORKS						
1	E/W Excavation in foundation in soft soil including lift 1.5m. and lead up to 10m all complete as per instruction of site incharge.	Cum	1.35				
2	Providing and laying P.C.C. 1:2:4 including curing all complete as per instruction of site incharge. (By using crush aggregate).	Cum	0.94				
3	Providing and laying brick masonry in 1:4 in walls, including curing all complete as instruction of site incharge.	cum	3.69				
4	Providing and laying 12.5 mm thick cement plaster in 1:4 c/s moarter including curing in wall all complete as per instruction of site incharge	sqm	67.40				
					Sub-Total (A)		
					13% Vat		
					Sub-Total including Vat (A)		
B)	NATURALLY VENTILATED TOP- VENT. POLYHOUSE						
5	Providing and installation of GI pipe constructed naturally ventilated polyhouse all complete as per instruction of site incharge.						
	Foundation base post (60 mm OD, 2mm thickness) 1m length	pcs	12.0				
	Side Post (60mm OD, 2 mm thick) 4m length	pcs	10.0				
	Centre Post (60mm OD, 2 mm thick) 6m length	pcs	2.0				
	small bottom pipe (2 mm thick, 1.5" 48 mm OD) 4m length	pcs	4.0				
	Big bottom pipe (2 mm thick, 1.5" 48 mm OD) 6m length	pcs	3.0				


 कृषि इन्जिनियर
 बाणगङ्गा नगरपालिका
 कार्यालय, बाणगङ्गा
 कैलाली प्रदेश, नेपाल


 माताराम मरासिनी
 प्रमुख प्रशासकीय अधिकृत



S.N.	Details of works	Unit	Quantity	Rate (Nrs.) Excluding VAT		Amount
				In Figures	In words	
	Bottom joiner pipe (2 mm thick, 1.5" 48 mm OD) 2m length	pcs	3.0			
	Center support pipe (2 mm thick, 1.5" 48 mm OD) 2m length	pcs	3.0			
	Cabin pipe (2 mm thick, 1.25" 42 mm OD) 4m length	pcs	4.0			
	Cabin pipe (2 mm thick, 1.25" 42 mm OD) 4m length	pcs	2.0			
	Cabin Pipe (2 mm thick, 1.25" 42 mm OD) 2.5m length	pcs	2.0			
	Lower Perlin pipe (2 mm thick, 1.25" 42 mm OD) 4m length	pcs	4.0			
	End Perlin pipe (2 mm thick, 1.25" 42 mm OD) 4m length	pcs	8.0			
	Top Perlin pipe (2 mm thick, 1.25" 42 mm OD) 4m length	pcs	4.0			
	Small Arc pipe (2 mm thick, 1.25" 42 mm OD) 4.25m length	pcs	5.0			
	Big Arc pipe (2 mm thick, 1.25" 42 mm OD) 5m length	pcs	5.0			
	cooling pad & fan support pipe (2 mm thick, 1.25" 42 mm OD) 6m length	pcs	3.0			
	cross column to column pipe (2 mm thick, 1" 32 mm OD) 5m length	pcs	8.0			
	cross arc to arc pipe (2 mm thick, 1" 32 mm OD) 5m length	pcs	4.0			
	Runner (0.75" 25 mm OD) 4m length	pcs	4.0			
	Member (0.75" 25 mm OD) 2m length	pcs	10.0			
	Member ii (0.75" 25 mm OD) 1.4m length	pcs	5.0			
	Member iii (0.75" 25 mm OD) 1.2m length	pcs	5.0			
	Apron Perlin (0.75" 25 mm OD) 4m length	pcs	11.0			
	Vent. Member (0.75" 25 mm OD) 0.9m length	pcs	5.0			
	Rolling Handle (0.75" 25 mm OD) 3m length	pcs	2.0			
	Curtain Pipe (0.5" 16 mm OD) 6m length	pcs	6.0			
6	Providing and installation of drip irrigation system including 1000 lts. PVC water tank, 1 Hp ISO certified motor, mainline 50mm pvc pipe, 50mm disk filter, 16mm lateral pipe all fitting and setup as per instruction of site incharge.	L/S	1.00			
7						
8	Providing and laying UV stabilized insect proof net (40 mesh to 40 mesh) all complete as per site instruction.	sqm	153.0			
9	Providing and laying U.V- stabilized Polyethylene film (cladding/cover materials) of 7 layer 200 micron thickness blocking, Anti drip/ fog, Diffused (Multi layer) for Top covering and side all complete as per instruction of site incharge.					
a)	U.V- stabilized Polyethylene film (cladding/cover materials) of 7 layer 200 micron	sqm	480.0			
b)	Apron	sqm	55.5			



कृषि इन्जिनियर
 कपिलवस्तु


नन्दिराम मर
 प्रमुख प्रशासकीय



S.N.	Details of works	Unit	Quantity	Rate (Nrs.) Excluding VAT		Amount	Rmks
				In Figures	In words		
10	Providing and fixing UV Stabilized Shade Net 50% inside green house with manual rolling or shifting system with support cables, pulleys, side support with clamps with manual collapsable arrangement. along with fixed thermal net on two longer sides of greenhouse all complete as per instruction of site incharge	sqm	138.6				
11	Aluminium locking profile with zig-zag spring, M10, M8, M6 nut bolt, clamps and other accessories						
	GI locking profile	rm	240				
	Galvanised Zigzag wire	rm	300				
	3/4" self/silt screw	pcs	650				
	4" bolt	pcs	36				
	3" bolt	pcs	30				
	2.5" bolt	pcs	24				
	1.5" bolt	pcs	170				
	10 mm nut	pcs	260				
	10 mm washer	pcs	260				
	I Bolt	pcs	20				
	60mm full clamps	pcs	60				
	42mm full clamps	pcs	30				
	76 mm half clamps	pcs	6				
	60 mm half clamps	pcs	30				
	42 mm half clamps	pcs	24				
	T fiture (32*32)	pcs	3				
	L fiture (32*32)	pcs	2				
	F bracket	pcs	10				
	L bracket	pcs	4				
	White pully	pcs	4				
	Curtain ring	pcs	80				
	Net joiner black	pcs	80				
	Curtain clamp (25mm)	pcs	40				
	Twisted wire	m	140				
	Polyster wire	m	90				
	Roll up universal joint (25mm)	pcs	2				
	Roolling joiner (16mm)	pcs	4				



 कृषि इन्जिनियर
 कृषि विकास विभाग, काठमाडौं


 भक्तिराम मरासिनी
 प्रमुख प्रशासकीय अधिकृत



S.N.	Details of works	Unit	Quantity	Rate (Nrs.) Excluding VAT		Amount	Rmks
				In Figures	In words		
12	Providing and fixing GI framed door all complete as per instruction of site incharge						
	Door	set	2.00				
	door kabja	pes	6.00				
	door chukul	pes	2.00				
	Chhkiny	pes	2.00				
	door handle	pes	4.00				
13	Providing and installation Cooling pad and exhaust fan all complete as per instruction of site incharge.						
a)	Complete set of cellulose cooling pad having aluminum frame 4 inch thickness 6.5 feet height x 5 ft width or 1.5*2 sqm with aluminium frame set. 0.5 hp electric motor (kirloskar/Crompton or equivalent) 500 lts. net capacity PVC water tank with inlet,outlet,overflow, cleanout hole etc.	set	3				
b)	Exhaust fan with stand single phase 50 inch in diameter	set	1				
c)	Electrification works (Electirc wire and MCB)	L/s	1				
d)	Installation of top vent greenhouse	sqm	128				
						Sub-Total (B)	
						13 % vat on each items of polyhouse.	
						Sub-Total (B) including 13% vat	
						Grand Total (A+B)	
	In Words:						

Contractor's Firm:
 PAN / VAT NO.:
 Seal:
 Proprietor's Name:
 Address:
 Tel/Mob no:

Stamp:

Signature:
 Date:

मतिराम मरासिनी
 प्रमुख प्रशासकीय अधिकृत

कृषि इंजिनियर
 कृषि तथा पशुधन विभाग, मद्रास
 कृषि विभाग, कापिलवस्तु
 कापिलवस्तु