



पत्र संख्या: ०८२/०८३  
चलानी नं.:

बाणगङ्गा नगरपालिका  
नगर कार्यपालिकाको कार्यालय  
बाणगङ्गा, कपिलवस्तु  
लुम्बिनी प्रदेश, नेपाल



मिति: २०८३/०१/२२

विषय: प्लाष्टिक टनेल (न्याचुरल्ली भेन्टिलेटेड टप भेण्ट ग्रीनहाउस) निर्माणको दररेट (कोटेशन) उपलब्ध गराई दिने बारेको म्याद थप सम्बन्धि सूचना।

प्रस्तुत विषयमा बाणगंगा नगरपालिकाको चालु आ.व. २०८२/०८३ को वार्षिक स्वीकृत कार्यक्रम अनुसार प्लाष्टिक टनेल (न्याचुरल्ली भेन्टिलेटेड टप भेण्ट ग्रीनहाउस) निर्माण गर्नु पर्ने भएकोले नगरपालिकामा सूचिकृत रहेका फर्म/कम्पनी/सप्लायर्सहरूले सम्लगन स्पेसीफिकेशन तथा डिजाईन अनुसारको प्लाष्टिक टनेल (न्याचुरल्ली भेन्टिलेटेड टप भेण्ट ग्रीनहाउस) निर्माण गर्न सकिने दररेट (कोटेशन) मिति २०८३/०१/०४ गतेको सूचनाद्वारा माग गरिएकोमा तोकिएको अवधि भित्र कुनै पनि कोटेशन दर्ता हुन नआएकोले ७ दिन (मिति २०८३/०१/२८ गते सम्म) सूचनाको म्याद थप गरिएकोले तोकिएको अवधि भित्र गोप्य सिलबन्दी गरी आवश्यक कागजात सहित दररेट (कोटेशन) उपलब्ध गराई दिनु हुन सम्बन्धित सरोकारवालाहरूमा यसै सूचनाद्वारा अनुरोध गरिन्छ।

सम्लगन गर्नुपर्ने आवश्यक कागजातहरू

१. फर्म/कम्पनी/सप्लायर्स दर्ता भएको दर्ता प्रमाण पत्रको प्रतिलिपी
२. आ.व. २०८१/०८२ को चुक्ता प्रमाण पत्रको प्रतिलिपी
३. स्थायी लेखा नम्बर (PAN/VAT) दर्ता प्रमाण पत्रको प्रतिलिपी
४. नागरिकताको प्रतिलिपी

नोट:- विस्तृत जानकारीका लागि बाणगंगा नगरपालिका, कृषि विकास शाखा कपिलवस्तुमा सम्पर्क राख्नुहोला।  
सम्पर्क नम्बर-९८४१३५२७४७, ९८४७२८४७००

भक्तिराम मरासिनी  
प्रमुख प्रशासकीय अधिकृत  
भक्तिराम मरासिनी  
प्रमुख प्रशासकीय अधिकृत



  
 Baggara Municipality  
 Office of Municipal Executive  
 Barzong, Kapilvastu  
 सुनसरी प्रदेश, नेपाल  
**Bill of Quantity**

Project Name: स्याचुरल्ली भेन्टिलेटेड टप भेट ग्रीनहाउस (कार्यालय परियर भित्र)



Project site: बाणगङ्गा नगरपालिका, नगर कार्यपालिकाको कार्यालय

A. The rate quoted under here shall be inclusive of:

1. Supplying the materials along with accessories to the site
2. Fixing and erecting them in position as per standard practices, specification and instruction of site Engineer
3. Tests and maintenance up to the period, specified in the agreement.

B. The itemwise rate should be quoted without vat.


S.N.	Details of works	Unit	Quantity	Rate (Nrs.) Excluding VAT		Amount	Rmks
				In Figures	In words		
<b>A) CIVILS WORKS</b>							
1	E/W Excavation in foundation in soft soil including lift 1.5m. and lead up to 10m all complete as per instruction of site incharge.	Cum	1.35				
2	Providing and laying P.C.C. 1:2:4 including curing all complete as per instruction of site incharge. (By using crush aggregate).	Cum	0.94				
3	Providing and laying brick masonry in 1:4 in walls, including curing all complete as instruction of site incharge.	cum	3.69				
4	Providing and laying 12.5 mm thick cement plaster in 1:4 o/s moarter including curing in wall all complete as per instruction of site incharge	sqm	67.40				
Sub-Total (A)							
13% Vat							
Sub-Total including Vat (A)							
<b>B) NATURALLY VENTILATED TOP- VENT. POLYHOUSE</b>							
5	Providing and installation of GI pipe constructed naturally ventilated polyhouse all complete as per instruction of site incharge.						
	Foundation base post (60 mm OD, 2mm thickness) 1m length	pes	12.0				
	Side Post (60mm OD, 2 mm thick) 4m length	pes	10.0				
	Centre Post (60mm OD, 2 mm thick) 6m length	pes	2.0				
	small bottom pipe (2 mm thick, 1.5" 48 mm OD) 4m length	pes	4.0				
	Big bottom pipe (2 mm thick, 1.5" 48 mm OD) 6m length	pes	3.0				

  
  
 कृषि इन्जिनियर

  
 प्रमुख प्रशासकीय अधिकृत



S.N.	Details of works	Unit	Quantity	Rate (Nrs.) Excluding VAT		Amount	Rmks
				In Figures	In words		
10	Providing and fixing UV Stabilized Shade Net 50% inside green house with manual rolling or shifting system with support cables, pulleys, side support with clamps with manual collapsible arrangement. along with fixed thermal net on two longer sides of greenhouse all complete as per instruction of site incharge	sqm	138.6				
11	Aluminium locking profile with zig-zag spring, M10, M8, M6 nut bolt, clamps and other accessories						
	GI locking profile	rm	240				
	Galvanised Zigzag wire	rm	300				
	3/4" self/silt screw	pes	650				
	4" bolt	pes	36				
	3" bolt	pes	30				
	2.5" bolt	pes	24				
	1.5" bolt	pes	170				
	10 mm nut	pes	260				
	10 mm washer	pes	260				
	1 Bolt	pes	20				
	60mm full clamps	pes	60				
	42mm full clamps	pes	30				
	76 mm half clamps	pes	6				
	60 mm half clamps	pes	30				
	42 mm half clamps	pes	24				
	T fiture (32*32)	pes	3				
	L fiture (32*32)	pes	2				
	F bracket	pes	10				
	L bracket	pes	4				
	White pully	pes	4				
	Curtain ring	pes	80				
	Net joiner black	pes	80				
	Curtain clamp (25mm)	pes	40				
	Twisted wire	m	140				
	Polyster wire	m	90				
	Roll up universal joint (25mm)	pes	2				
	Roolling joiner (16mm)	pes	4				

  
 ಕೆ.ಎಸ್.ಇಂಜಿನಿಯರಿಂಗ್  
 ಕೃಷಿ ಇಂಜಿನಿಯರಿಂಗ್  
 ಬೆಂಗಳೂರು

  
 ಅಂತಿರಾಮ ಮರಾಸಿನಿ  
 ಪ್ರಾಜೆಕ್ಟ್ ಪ್ರಾಜಾಕ್ಟಿವ್ ಅಧಿಕಾರಿ



S.N.	Details of works	Unit	Quantity	Rate (Nrs.) Excluding VAT		Amount
				In Figures	In words	
	Bottom joiner pipe (2 mm thick, 1.5" 48 mm OD) 2m length	pes	3.0			
	Center support pipe (2 mm thick, 1.5" 48 mm OD) 2m length	pes	3.0			
	Cabin pipe (2 mm thick, 1.25" 42 mm OD) 4m length	pes	4.0			
	Cabin pipe (2 mm thick, 1.25" 42 mm OD) 4m length	pes	2.0			
	Cabin Pipe (2 mm thick, 1.25" 42 mm OD) 2.5m length	pes	2.0			
	Lower Perlin pipe (2 mm thick, 1.25" 42 mm OD) 4m length	pes	4.0			
	End Perlin pipe (2 mm thick, 1.25" 42 mm OD) 4m length	pes	8.0			
	Top Perlin pipe (2 mm thick, 1.25" 42 mm OD) 4m length	pes	4.0			
	Small Arc pipe (2 mm thick, 1.25" 42 mm OD) 4.25m length	pes	5.0			
	Big Arc pipe (2 mm thick, 1.25" 42 mm OD) 5m length	pes	5.0			
	cooling pad & fan support pipe (2 mm thick, 1.25" 42 mm OD) 6m length	pes	3.0			
	cross column to column pipe (2 mm thick, 1" 32 mm OD) 5m length	pes	8.0			
	cross arc to arc pipe (2 mm thick, 1" 32 mm OD) 5m length	pes	4.0			
	Runner (0.75" 25 mm OD) 4m length	pes	4.0			
	Member (0.75" 25 mm OD) 2m length	pes	10.0			
	Member ii (0.75" 25 mm OD) 1.4m length	pes	5.0			
	Member iii (0.75" 25 mm OD) 1.2m length	pes	5.0			
	Apron Perlin (0.75" 25 mm OD) 4m length	pes	11.0			
	Vent. Member (0.75" 25 mm OD) 0.9m length	pes	5.0			
	Rolling Handle (0.75" 25 mm OD) 3m length	pes	2.0			
	Curtain Pipe (0.5" 16 mm OD) 6m length	pes	6.0			
6	Providing and installation of drip irrigation system including 1000 lts. PVC water tank, 1 Hp ISO certified motor, mainline 50mm pvc pipe, 50mm disk filter, 16mm lateral pipe all fitting and setup as per instruction of site incharge.	L/S	1.00			
7						
8	Providing and laying UV stabilized insect proof net (40 mesh to 40 mesh) all complete as per site instruction.	sqm	153.0			
9	Providing and laying U.V- stabilized Polyethylene film (cladding/cover materials) of 7 layer 200 micron thickness blocking, Anti drip/ fog, Diffused (Multi layer) for Top covering and side all complete as per instruction of site incharge.					
a)	U.V- stabilized Polyethylene film (cladding/cover materials) of 7 layer 200 micron	sqm	480.0			
b)	Apron	sqm	55.5			

ಕೃಷಿ ಇಂಜಿನಿಯರ್

ಪ್ರಮುಖ ಪ್ರಾಜಾಸಕ್ತಿಯ